

DAM OUTLETS HYDROPOWER SITES IDENTIFIED BY AHEC

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
1	Upper Narmada (LBCH)	DPR Ready	Dindori	81°23'20" E 22°51'50" N	3.8	13.52	400	312	2.10	2.67
2	Upper Narmada (RBCH)	DPR Ready	Dindori	81°23'20" E 22°51'50" N	4.23	8.58	300	246	1.57	2.82
3	Matiyari (LBCH)	Completed	Mandla	80°34'30" E 22°31'45" N	6.77	6.17	350	262	1.53	3.10
4	Matiyari (RBCH)	Completed	Mandla	80°34'30" E 22°31'45" N	6.6	5.76	300	225	1.31	3.10
5	Majhgaon	Completed	Mandla	80°30'40" E 23°3'20" N	4.42	0.87	50	42	0.13	5.8
6	Bichhiya	Completed	Mandla	80°42'00" E 22°27'00" N	4.56	2.81	100	81	0.35	4.16
7	Dhuandhar	Completed	Mandla	80°18'10" E 22°27'40" N	4.77	1.47	50	41	0.13	5.67
8	Upper Burhner (LBCH)	Proposed	Mandla	80°59'05" E 22°32'36" N	5.81	5.52	250	198	0.99	3.60
9	Upper Burhner (RBCH)	Proposed	Mandla	80°59'05" E 22°32'36" N	4.91	1.13	50	41	0.20	3.69
10	Halon	DPR Ready	Mandla	80°47'30" E 22°22'30" N	4.83	13.90	550	429	2.17	3.55

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
11	Dobatoria (LBCH)	Proposed	Mandla	80°28'00" E 22°19'10" N	4.10	1.38	50	42	0.20	3.78
12	Dobatoria (RBCH)	Proposed	Mandla	80°28'00" E 22°19'10" N	4.80	5.06	200	162	0.79	3.37
13	Sampna	Completed	Betul	77°59'05" E 21°15'15" N	5.3	3.0	150	121	0.52	4.2
14	Bargi Diversion (RBCH)	On-going	Jabalpur	79°55'33" E 22°56'30" N	7.99	227.44	15000	9900	78.84	2.26
15	Barnoo	Completed	Jabalpur	80°07'10" E 23°20'50" N	7.74	3.45	200	158	0.70	4.0
16	Madai	Completed	Jabalpur	80°10'20" E 23°04'30" N	5.29	1.61	50	41	0.13	5.6
17	Atariya	Proposed	Jabalpur	80°17'00" E 23°25'00" N	7.14	7.74	450	346	1.77	3.52
18	Bahoribund (LBCH)	Completed	Jabalpur	80°07'23" E 23°42'00" N	3.68	1.5	50	41	0.13	5.6
19	Bahoribund (RBCH)	Completed	Jabalpur	80°07'23" E 23°42'00" N	4.72	0.78	50	41	0.13	5.67
20	Pariat	Completed	Jabalpur	80°10'00" E 23°15'00" N	8.43	0.5	50	38	0.42	1.63
21	Sher	Proposed	Narsinghpur	79°24'45" E 22°50'15" N	6.25	3.3	150	118	0.66	3.22
22	Macharewa	Proposed	Narsinghpur	79°20'15" E 22°49'15" N	10.25	3.72	300	219	1.31	3.0

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
23	Shakkar	Proposed	Narsinghpur	79°03'30" E 22°46'00" N	22.50	24.6	4600	2300	20.15	2.05
24	Dudhi	Proposed	Narsinghpur	78°41'00" E 22°43'00" N	13.16	14.14	1550	978	6.79	2.59
25	Tawa (RBCH)	Completed	Hoshangabad	78°09'30" E 22°37'38" N	10.65	26.77	2350	1480	9.26	2.87
26	Dokarikheda	Completed	Hoshangabad	78°22'00" E 22°39'00" N	6.89	1.87	100	79	0.26	5.47
27	Morand	Identified	Hoshangabad	77°29'00" E 22°19'15" N	11.15	16.77	1550	1079	5.43	3.56
28	Mogha	Completed	Raisen	78°40'14" E 23°08'42" N	10.75	1.45	100	75	0.28	4.8
29	Upper Palakmatti	Completed	Raisen	77°53'45" E 23°11'36" N	12.62	3.54	350	252	1.22	3.72
30	Lower Palkamatti	Completed	Raisen	77°54'45" E 23°10'30" N	6.98	2.56	150	118	0.52	4.10
31	Ganjal (LBCH)	Proposed	Harda	77°19'55" E 22°13'45" N	9.78	7.13	550	396	1.93	3.69
32	Ganjal (RBCH)	Proposed	Harda	77°19'55" E 22°13'45" N	9.78	1.38	100	74	0.35	3.8
33	Imlidhana	Proposed	Harda	78°58'43" E 22°02'46" N	5.0	1.8	50	41	0.13	5.6
34	Chandra-Kesher (LBCH)	Completed	Dewas	76°32'30" E 22°37'00" N	4.64	3.87	150	123	0.79	2.80

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
35	Chandra-Kesher (RBCH)	Completed	Dewas	76°32'30" E 22°37'00" N	5.23	1.14	50	41	0.26	2.84
36	Paras	Completed	Dewas	76°28'00" E 22°33'00" N	4.89	1.17	50	41	0.13	5.6
37	Choral	Completed	Indore	75°45'00" E 22°25'00" N	4.95	3.5	150	121	0.43	5.10
38	Nakheri	Completed	Indore	75°45'00" E 22°27'30" N	3.91	3.5	100	84	0.26	5.8
39	Kolar Barrage (LBCH)	Completed	Sheore	77°26'45" E 22°53'30" N	1.14	16.4	150	136	0.52	4.7
40	Kolar Barrage (RBCH)	Completed	Sheore	77°26'45" E 22°53'30" N	1.14	18.6	150	136	0.52	4.7
41	Seep Kolar Link	Proposed	Sheore	77°04'14" E 22°54'02" N	1.5	10	100	90	0.26	6.2
42	Lower Kolar	Proposed	Sheore	77°26'45" E 22°53'30" N	14.10	35	4000	2120	14	2.72
43	Ghoghara	Proposed	Sheore	77°04'04" E 22°46'33" N	4.67	6.39	250	198	0.66	5.4
44	Gadigaltar	Completed	Khargone	75°44'40" E 21°38'20" N	3.7	1.89	50	42	0.17	4.45
45	Navalpura	Completed	Khargone	75°04'45" E 21°56'24" N	3.85	0.83	50	41	0.13	5.6
46	Dejla-Dewada	Completed	Khargone	75°37'30" E 21°36'45" N	7.21	6.30	350	259	1.23	3.79

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
47	Satak	Completed	Khargone	75 ⁰ 32'00" E 23 ⁰ 03'00" N	3.75	1.82	50	41	0.13	5.6
48	Jhirbhar	Completed	Khargone	75 ⁰ 48'50" E 20 ⁰ 06'20" N	3.63	1.20	50	41	0.13	5.6
49	Upper Beda	On-going	Khargone	75 ⁰ 58'50" E 21 ⁰ 45'00" N	5.38	7.5	350	280	1.38	3.65
50	Segwal	Completed	Khargone	70 ⁰ 22'00" E 22 ⁰ 03'00" N	3.5	0.97	50	41	0.13	5.6
51	Sipton	Completed	Khargone	75 ⁰ 41'30" E 22 ⁰ 00'30" N	3.65	2.0	50	41	0.13	5.6
52	Ambak	Completed	Khargone	75 ⁰ 49'30" E 22 ⁰ 00'30" N	4.05	1.50	50	41	0.13	5.6
53	Sukta	Completed	Khandwa	76 ⁰ 16'00" E 21 ⁰ 36'00" N	5.82	7.75	350	273	1.84	2.67
54	Chhota Tawa (LBCH)	Proposed	Khandwa	76 ⁰ 27'06" E 21 ⁰ 48'12" N	5.27	1.45	50	41	0.13	5.6
55	Ralawati (LBCH)	Completed	Barwani	75 ⁰ 12'20" E 21 ⁰ 35'10" N	4.75	1.06	50	41	0.13	5.6
56	Ralawati (RBCH)	Completed	Barwani	75 ⁰ 12'20" E 21 ⁰ 35'10" N	4.75	1.06	50	41	0.13	5.6
57	Lower Goi (RBCH)	Proposed	Barwani	74 ⁰ 55'30" E 21 ⁰ 54'30" N	18.13	10.60	1600	960	7.0	2.47
58	Man (LBCH)	Completed	Dhar	75 ⁰ 05'40" E 22 ⁰ 24'20" N	14.32	3.34	400	276	2.63	1.90

S. No.	Name of Dam Project	Status of Dam	Location Of Scheme		Design Head (m)	Design Discharge (Cumec)	capacity (kW)	Project Cost	Annual Energy	Generation Cost/Unit
			District	Geographical Coordinates				Rs. (lacs)	(MU)	Rs.
59	Man (RBCH)	Completed	Dhar	75°05'40" E 22°24'20" N	14.22	8.28	950	617	6.24	1.78
60	Sakelda	Completed	Dhar	75°19'30" E 22°16'30" N	3.79	1.37	50	41	0.13	5.6
61	Mod Sagar	Completed	Jhabua	74°31'45" E 22°34'42" N	4.0	1.47	50	42	0.13	5.8
62	Jobat	Completed	Jhabua	74°35'10" E 20°16'50" N	6.85	7.57	400	304	1.75	3.10
63	Dhamoi	Identified	Jhabua	74°44'35" E 22°27'20" N	7.13	1.7	100	78	0.26	5.4
Total Power Potential							40800			